

CHAMPAIGN PARK DISTRICT

NOTICE FOR BIDS

Public notice is hereby given that the Champaign Park District (District) will receive sealed bids for all labor and materials to install new epoxy coatings and concrete repairs at the Sholem Aquatic Center pools until 11:00 am Central Standard Time on July 21st, 2026 at the District offices, located at 706 Kenwood Road, Champaign, IL 61821, (217) 819-3812 at which time such bids will be opened and publicly read aloud.

Bid packets will be available at the District's website bid tab (<https://champaign-parks.org/bids-rfps>) beginning June 29th, 2026 or by emailing Alexandra.kolar@champaignparks.org.

Bids are required to be submitted under a condition of irrevocability for a period of thirty (30) days after submission. The District reserves the right to reject any or all bids, waive any or all informalities in the bids, and determine the lowest responsible bidder. The District encourages minority business firms to submit bids for the project. Bidders shall provide the services and materials in a good and workmanlike, professional and courteous manner. All bidders shall comply with provisions of the District Affirmative Action Ordinance and ensure that any subcontractor shall also comply therewith. Furthermore, all bidders shall comply with all federal, state, and local requirements pertaining to the Illinois Prevailing Wage Act, the Illinois Human Rights Act, equal opportunity regulations, and any other state or federal regulations applicable to the project and contract. All bidders are notified that the District will affirmatively assure that the contract will be awarded without discrimination on the grounds of race, color, religion, national origin, and any other protected class or characteristics, and no person shall be excluded from participation in, denied the benefits of, or otherwise subjected to discrimination under any program, service, or activity in violation of any applicable federal or state laws prohibiting such discrimination.



June 29th, 2026

Dear Potential Bidder:

The Champaign Park District is requesting bids for all labor, materials, and equipment to install epoxy coatings and concrete repairs at the Sholem Aquatic Center pools in Champaign, IL. Enclosed is a copy of the bid information.

A non-mandatory pre-bidders meeting conference will be held on Tuesday, July 7th at 8 am at the Sholem Aquatic Center located at 2205 Sangamon Dr, Champaign, IL.

Sealed bids shall be delivered or mailed to Ally Kolar, Champaign Park District, 706 Kenwood Road, Champaign, Illinois 61821 by **11:00 am prevailing time on Tuesday, July 21st, 2026**. Sealed bid packets shall be clearly marked with the words: "**Bid Document: SHOLEM EPOXY**", along with the bidder's name and address, on the outside of the envelope.

When submitting your sealed bid, please make sure to enclose the following:

1. Bid Forms (page 6-10)
2. Commitment to Engage in Affirmative Action Practices (page 11)
3. Affirmative Action Contractor's Compliance Report (page 12-13)

If you have any questions regarding the areas, or any of the enclosed information please contact me at 217-819-3812, 7:30 a.m. to 4:00 p.m., weekdays, or alexandra.kolar@champaignparks.com

Sincerely,

Ally Kolar
Construction Project Manager

Champaign Park District
706 Kenwood Road
Champaign, Illinois 61821-4112
217.398.2550 Phone
217.355.8421 Fax
www.champaignparks.org

Park Commissioners
Craig W. Hays
Barbara J. Kuhl
Tyler R. Rouse
Jane L. Solon
Michael R. Somers

Officers
Marguerite Bailey, *Secretary*
Guy C. Hall, *Attorney*
Donna K. Lawson, *Treasurer*
Sarah Sandquist, *Executive Director*

Our mission is to enhance our community's quality of life through positive experiences in parks, recreation, and cultural arts.

Champaign Park District: Invitation for Bids Sholem Concrete Repairs and Epoxy

SECTION I. INSTRUCTIONS TO BIDDERS

- 1.01 Invitation to Bid: The Champaign Park District is requesting bids from contractor(s) to furnish all labor, material, supplies and equipment to install new epoxy coatings and concrete repairs at the Sholem Aquatic Center pools located at 2205 Sangamon Dr, Champaign, IL, 61821.
- 1.02 Due Date: Sealed bids shall be delivered or mailed to **Ally Kolar, Champaign Park District, 706 Kenwood Road, Champaign, Illinois 61821, by 11:00 a.m.** prevailing time on **Tuesday, July 21st, 2026**, at which time bids will be opened and publicly read. Facsimile copies and late bids will not be accepted.
- 1.03 Pre-Bidders Conference: **A non-mandatory pre-bidders conference will be held on Tuesday, July 7th at 8 am at the Sholem Aquatic Center located at 2205 Sangamon Dr, Champaign, Illinois 61821.** The purpose of the pre-bid conference is to provide a structured and formal opportunity for the District to accept questions from potential bidders on the bid documents as well as clarify the contents of the Bid. Any major revisions to the Bid as a result of the pre-bid conference, or answers to deferred questions, shall be made in the form of a written addendum to the original Bid.
- 1.04 Bid Understanding: By submitting a bid, the bidder agrees and assures that the specifications are adequate, and the bidder accepts the terms and conditions, specifications and requirements of work to be completed. Failure to do so will be at the bidder's risk and they cannot secure relief on the plea of error.
- 1.05 Submission of Bid: All bids shall be submitted on the **Bid Forms (Page 11)** and accompanied by requested information including the **Champaign Park District Commitment to Engage in Affirmative Action Practices forms (Pages 12-13)**. All blank spaces shall be properly filled in, in ink or typewritten, in both words and figures, and with no other conditions, changes, erasures or interlineations. Bids shall be signed and executed by a principal duly authorized to make contracts.
- Bids shall be enclosed in an envelope sealed and clearly marked with the words: **"BID DOCUMENT: SOLEM EPOXY."** The bidder shall put their name and address on the outside of the envelope.
- The Champaign Park District shall not be responsible for the premature opening of bid envelopes, which are not properly filled out in accordance with the instructions.
- 1.06 Site Visits: It shall be the sole responsibility of the bidder to inspect the location(s) prior to submitting a bid. No variation in price or conditions shall be permitted based upon a claim of ignorance. Submission of a bid shall be considered evidence that the bidder has familiarized himself/herself with the nature and extent of the work, and the equipment, materials and labor required.
- 1.07 Awards Criteria: Award will be to the lowest priced, responsible bidder if all other requirements are satisfactorily met. Bidder must include three (3) commercial references of comparable nature to location bid on. The Champaign Park District reserves the right to reject any and all bids, waive technicalities and irregularities and/or to award the contract only to a bidder who is equipped, competent and experienced in the class of work and whose bid is deemed to be advantageous to the interests of the Champaign Park District.
- 1.08 Rejection of Bids: The Park District reserves the right to reject any, all, or any part of a bid, and waive any or all irregularities and select the bid that is in its best interest. The Park District reserves the right to reject the bid of any bidder who previously failed to perform adequately for the Park District or any other governmental agency or company.

Champaign Park District: Invitations for Bids for Sholem Concrete Repairs and Epoxy

- 1.09 Withdrawal: Bidder may make a written request to modify or withdraw the offer at any time prior to the opening. Bids may not be modified after submittal or withdrawn or modified after bid opening. Withdrawal of bids will be allowed if award of contract has been delayed more than 60 days, after date of actual bid opening.
- 1.10 Inquiries: Questions and comments regarding this solicitation should be directed to the **Ally Kolar, Construction Project Manager** at Bresnan Meeting Center, 706 Kenwood Road, Champaign, Illinois 61821 or by emailing Alexandra.kolar@champaignparks.org or by calling **217-819-3812**. Written answers to questions of a general nature or which would affect the solicitation will be provided to all eligible bidders. Only written answers to the questions shall be binding. Inquiries must be received by **3 pm on Wednesday, July 15th, 2026**. Written responses to questions or bid addenda will be posted to the Champaign Park District "Bids & RFPs" web page by **4 pm prevailing time on Thursday July 16th, 2026**. It is the bidders' responsibility to check for bid addenda and written responses to questions.

SECTION II. TERMS AND CONDITIONS

- 2.01 Definitions: *Owner* shall mean the Champaign Park District. *Contractor* shall mean party of the second part to this contract, acting directly or through his or its legal representative(s) or agent(s). *Subcontractor* shall mean persons, firms or corporations having a direct contract with the contractor, and those who contract to furnish labor or labor and materials at the site of the project.
- 2.02 Contract Documents: The contract entered into by the parties shall consist of the Instructions to Bidder, Terms and Conditions, Specifications, and Fence Repair Bid Forms including all modifications thereof, and a purchase order, if applicable, requiring signatures of the Champaign Park District and the Contractor, all of which shall be referred to collectively as the Contract Documents.
- 2.03 Payments: Contractor shall submit invoice to the District by the 1st Friday of the month. Invoice must include the Purchase Order number. Payment will be monthly after Board approval of the bills, which is the 2nd Wednesday of each month.
- 2.04 Taxes: The District is exempt from any taxes imposed by State and/or Federal Government. Exemption certificates will be provided upon request.
- 2.05 Cancellation/Termination: The Park District may cancel this contract for convenience by providing thirty (30) calendar days advance notice to the contractor.

The Park District may cancel this contract for cause (i.e., fails to meet deadlines, fails to provide agreed upon service, etc.) at any time by giving one week's written notice to the contractor. The termination of the contract will be issued only after the District deems that the contractor has failed to remedy the problem after being forewarned.

The Contractor may cancel this contract for convenience or cause by providing thirty (30) calendar days advance notice to the District.

- 2.06 Compliance or Deviation to Specifications: Bidder hereby agrees that the equipment or services offered will meet all the requirements of the specifications in this solicitation unless deviations from them are clearly indicated in the Bidder's response. Bidder may submit an attachment entitled "Exceptions for Specification", which must be signed by Bidder's authorized representative. An explanation must be made for each item to which an exception is taken, giving in detail the extent of the exception and the reason for which it is taken. Bids failing to comply with this requirement will be considered non-responsive.

Champaign Park District: Invitation for Bids Sholem Concrete Repairs and Epoxy

- 2.07 Compliance with Ordinances and Statutes and Notice of Special Conditions: Every bidder shall comply with the requirements of the Affirmative Action Regulations of the Champaign Park District, Illinois Fair Employment Act, Equal Opportunity regulations and other Federal and State of Illinois regulations and guidelines applicable to the contract.
- 2.08 Assignment and Subcontracts: The Contractor shall not assign this contract or any part thereof without written consent of the Park District, nor shall the Contractor award any work under this contract to any subcontractor without prior written approval from the Director of Operations or the Executive Director. Nothing contained in the contract documents shall create a contractual relation between any subcontractor and the Owner. Any subcontractor assigned must meet the same requirements as the Contractor awarded the bid.
- 2.09 Independent Contractor: The contractor acknowledges and agrees that the Contractor is not an employee of the Park District, is not entitled to any benefits or protections afforded employees of the Park District, nor bound by any obligations of employees of the Park District. Nevertheless, the Contractor will not act contrary to the policies of the Park District. The Contractor understands and fully agrees that the Contractor will not be insured under provisions of the unemployment compensation insurance of the Park District or the workers' compensation insurance of the Park District, and that any injury or property damage in connection with the work performed will be the Contractor's sole responsibility and not that of the Park District. It is also understood that the Contractor is not protected as an employee or as a person acting as an agent or employee under the provisions of the general liability insurance of the Park District and, therefore, the Contractor will be solely responsible for the Contractor's own acts or omissions, and those of the Contractor's employees and agents, if any. The Park District will not in any manner whatsoever be obligated to defend, indemnify or hold harmless the Contractor, or the Contractor's employees and agents, if any, in matters of liability.
- 2.10 Indemnification: Contractor shall indemnify and hold harmless District and its officers, officials, employees, volunteers and agents from and against all claims, damages, losses and expenses, including but not limited to legal fees (attorneys' and paralegals' fees and court costs) arising out of or resulting from the performance of Contractor's work, provided that any such claim, damage, loss or expense (i) is attributable to bodily injury, sickness, disease or death, or injury to or destruction of tangible property, including the loss of use therefrom, and (ii) is caused in whole or in part by any wrongful or negligent act or omission of Contractor, any Subcontractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, except to the extent it is caused in part by a party indemnified hereunder. Such obligation shall not be construed to negate, abridge, or otherwise reduce any other right or obligation of indemnification which would otherwise exist as to any party or person described in this Paragraph. Contractor shall similarly protect, indemnify and hold and save harmless District, its officers, officials, employees, volunteers and agents against and from any and all claims, costs, causes, actions and expenses including but not limited to legal fees, incurred by reason of Contractor's breach of any of its obligations under, or Contractor's default of, any provision of the Agreement.
- 2.11 Insurance: The Contractor shall purchase and maintain such insurance as will protect him/her from claims under worker's compensation acts and from claims or damages because of bodily injury, including death, and all property damage, including without limitation, which might arise during operations under this contract, whether such operations be by himself/herself or by any subcontractor or anyone directly or indirectly employed by either of them. After award of bids by the Park Board of Commissioners at their Regular Board Meeting, **Contractor shall provide a Certificate of Insurance.** Each sequential year of this contract the insurance requirements must be turned in for same time period corresponding to the dates above. Failure to do so will result in loss of the contract, which will be awarded to the next lowest responsible bidder. Contractor shall maintain minimum limits of insurance no less than:

Champaign Park District: Invitations for Bids for Sholem Concrete Repairs and Epoxy

- (a) Workman's Compensation as required by statute and Employers Liability Insurance: Employers Liability limits shall not be less than \$1,000,000 each accident for bodily injury by accident or \$1,000,000 each employee for bodily injury by disease.
- (b) General Liability: a limit of not less than \$2,000,000 each occurrence
- (c) Automobile Liability: limit of not less than \$2,000,000 each accident

Failure to maintain the required insurance may result in termination of this Contract.

- 2.12 Bid Rigging or Bid Rotating: The bidder by affixing his or her signature to the bid, certifies that he/she has not been barred from being awarded a contract with a unit of State or local government as a result of a violation of Section 33E-3 or 33E-4 of the Criminal Code of 1961.
- 2.13 Sexual Harassment Policy: Contractor certifies that it has a written sexual harassment policy that includes the following information:
 - a. The illegality of sexual harassment.
 - b. The definition of sexual harassment under State Law.
 - c. A description of sexual harassment utilizing examples.
 - d. The Contractors internal complaint process including penalties.
 - e. The legal recourse, investigative and complaint process available through the Illinois Department of Human Rights and Equal Employment Opportunity Commission.
 - f. Protection against retaliation against a person because he or she has opposed that which he or she reasonably and in good faith believes to be sexual harassment or because he or she has made a charge, filed a complaint, testified, assisted, or participated in an investigation, proceedings or hearing under the Illinois Human Rights Act or any other civil rights statute.

A copy of the policies shall be provided to the District upon request.

- 2.14 Protest: If bidder objects to any provision of the bid, believes the District improperly rejected your offer, or believes the selected offer is not in the Champaign Park District's best interests, bidder may submit a written protest to the Executive Director within five (5) days after the opening. Owner will consider only written protests that are properly and timely filed with the District. Owner will issue a written decision and that decision is final.
- 2.15 Bid Security: Each bid must be accompanied by a certified cashier's check, certified check, or a bid bond duly executed by the bidder as principal and having as surety thereon a surety company approved by the Owner, in the amount of 10% of the total bid. Such cash, checks, or bid bonds will be returned to all except the three lowest bidders within three (3) days after the opening of bids, and the remaining cash, checks, or bid bonds will be returned promptly after the Owner and the accepted bidder have executed the contract, or, if no award has been made within thirty (30) days after the date for the opening of bids, upon demand of the bidder at any time thereafter, so long as he has not been notified of the acceptance of his/her bid.

SECTION III. GENERAL INFORMATION

- 3.1 Contractor shall provide all labor, materials, equipment and supervision to perform work installation of new epoxy coatings and concrete repairs at the Sholem Pools.
- 3.2 Scope is dictated in Exhibit A. Pools include (5) pools identified as the lap pool, activity pool, lazy river, plunge pool, and kiddie pool. Refer to provided design drawing plans for dimensioning. Note that the lap pool and activity pool are connected. Bidder is responsible for verifying any quantities provided. Layout drawings have been provided.
- 3.3 Contractor shall provide 5-year warranty materials and workmanship from date of substantial completion.

Champaign Park District: Invitation for Bids Sholem Concrete Repairs and Epoxy

- 3.4 Contractor shall provide pricing for the following (1) lump sum pricing for all project scope and (2) alternate #1 unit pricing for any concrete repatching work that exceeds an anticipated 600 SF value, as agreed upon by Owner.
- 3.5 Contractor shall coordinate with owner to schedule work around planned programming and other Sholem maintenance projects. Intent is for work to commence after pools are drained following the 9/7/2026 Labor Day holiday.
- 3.6 Final payment will be made after completion and acceptance of the project by the Construction Project Manager.
- 3.7 Substantial completion of installation work to be completed by November 20th, 2026.

SECTION IV: SPECIFICATIONS

- 4.01 It is the responsibility of each bidder to view each site. Bid prices in response to this solicitation shall be firm for the full term of the contract. Contract bid areas are as defined on the attached Exhibit A included in the bid package.
- 4.02 Pool tiles should be protected during blasting procedures and new installations. Any existing pool tile damaged or loosened during new installation procedures shall be replaced to match the existing.
- 4.03 Steps and floors less than 5' depth to have anti-slip finish.
- 4.04 Owner shall remove, store, and reinstall drain covers.
- 4.05 SPECIFIED PRODUCTS:

For new epoxy coatings, use Tnemac Series N69F High Build Epoxoline II. See provided product data sheet.

Install Series 215 Surfacing Epoxy for patching, spalling, chipping, and other surface anomalies. See provided product data sheet.

- 4.06 COATING SURFACE PREPARATION:

All preexisting layers of epoxy coatings on pool walls, floor, and borders must be abrasive blasted down to concrete base.

All existing coating shall be removed by abrasive blast cleaning. All coatings shall be removed and all surfaces shall be uniformly roughened to a degree similar in appearance to a medium to coarse grade/grit sandpaper, in accordance with the International Concrete Repair Institutes (ICRI) Guideline # 03730, CSP3 or CSP4.

Protect and cover all floor drains, gutter drains, escutcheons and stainless steel during blasting and cleaning operations.

Remove and replace with new, all failed gutter sealant.

Clean up spent abrasive and debris and properly dispose of off-site. A contractor supplied roll off dumpster can be located on-site.

Apply a TSP (Tri Sodium Phosphate) solution with scrub brushes to all surfaces and pressure wash rinse clean.

Champaign Park District: Invitations for Bids for Sholem Concrete Repairs and Epoxy

Acceptable surfaces shall be free of laitance, form release agents, curing agents, oil, grease, and other contaminants. The surface shall be free of fins, projections, loosely adhering concrete, dirt, and dust particles.

All voids, gouges, bugholes and other surface anomalies shall be repaired in accordance with the Coating Application procedures listed below.

The presence of moisture in the concrete shall be checked in accordance with ASTM D 4263-88: Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method. Moisture must be absent prior to application of coatings.

Quality Assurance: following removal of existing pool coatings, contractor shall arrange for quality inspection of the pool surface with the pool paint manufacturer's representative. Contractor shall submit a letter of approval of condition from the representative prior to application of new coating. Provide manufacturer with required estimated square footage to ensure proper material usage.

4.07 APPLICATION OF NEW COATINGS:

All surfaces must be clean and dry, prior to the application of coatings.

First Coat: Apply one complete coat of Tnemec Series N69 Hi-Build Epoxoline II at a spreading rate of 400 square feet per gallon. Thin first coat 10% with Tnemec #4 thinner.

After first coat has cured, fill all voids, gouges, bugholes and other surface anomalies with Tnemec Series 218 MortarClad or Series 215 Surfacing Epoxy, depending on depth to be filled. Note: Tnemec Series 211-0211 fumed silica may be added to Series 215 Surfacing Epoxy at 0.75:1 by volume per mixed gallon where a thicker consistency is required to achieve the desired application and film build properties.

Second Coat: Apply one complete coat of Tnemec Series N69-Color* Hi-Build Epoxoline II at a spreading rate of 350 square feet per gallon (3 dry mils).

Slip resistance – if desired by Owner, broadcast slip resistant aggregate into the 2nd coat while wet. Sweep off excess prior to topcoating.

Third Coat: Apply one complete coat of Tnemec Series N69-Color* Hi-Build Epoxoline II at a spreading rate of 350 square feet per gallon (3 dry mils).

Apply two coats (Series N69) for striping, targets, and lane lines.

*Color to be P006 Delft Blue-Pool by Tnemec

4.08 CONCRETE PATCHING

Perform 600 SF of work for concrete repatch locations. This value accounts for several locations specifically identified in Exhibit A that include known spalling, holes to fill, and areas of previous in-house concrete patching expected to be stripped down during blasting and requiring repatch and anticipated leveling for joint rework.

4.09 POOL JOINTS

Remove and replace all floor to wall joints in the Lazy River pool and designated locations for the lap pool and activity pool per Exhibit A. Remove and repatch surfacing around joint for appropriate rehabilitation leveling at a 1' width each side of joint.

BID FORMS

MAIN BID COST: _____

ALTERNATE #1 CONCRETE PATCHING UNIT COST: _____

EXPECTED PROJECT DURATION: _____

Insurance Statement: By signing the bid documents, bidder hereby certifies that the bidder has reviewed and understands the insurance coverage requirements specified in the Bid specifications.

I hereby certify that I am duly authorized to sign as a representative for the contractor submitting the attached bid to the Champaign Park District, and that they have read, fully understand, and accept the items detailed in this bid.

Signed this _____ day of _____, 20____.

SUBMITTED BY:

Company

Address

Phone Fax

Cell

Email

Authorized Agent (print or type)

Signature of Authorized Agent

FIN or SS # _____

Champaign Park District: Invitations for Bids for Sholem Concrete Repairs and Epoxy

References: Please provide a list of three (3) references including contact person, company name, address, phone number and a brief scope of work below:

Name: _____ Phone #: _____
Company _____
Address _____
Scope of Work: _____

Name: _____ Phone #: _____
Company _____
Address _____
Scope of Work: _____

Name: _____ Phone #: _____
Company _____
Address _____
Scope of Work: _____

SECTION V: COMMITMENT TO ENGAGE IN AFFIRMATIVE ACTION PRACTICES

A. The undersigned bidder/contractor/supplier/vendor understands and agrees:

It is the policy of _____ *(name of company)* that all applicants for employment and all employees be recruited, hired and assigned on the basis of merit without discrimination because of race, creed, color, national origin, sex, age or disability. The employment practices of this company have been and will continue to be such as to insure that all employees are treated equally and that no distinctions are made in rates of pay, benefits or opportunities for advancement.

Therefore employment of individuals, their assignment to jobs, their transfers and their promotions shall be determined by matching the requirements of an open position with the candidate's skills and qualifications without regard to race, creed, color, national origin, sex, age or disability.

All management and supervisory personnel shall continue to take positive action to insure that all principles and objectives of the affirmative action program are complied with to carry out the provisions of the laws governing non-discrimination in employment.

- B. The undersigned bidder/contractor/supplier/vendor understands and agrees: to submit to the park district upon request written evidence of the effectiveness of the above-required practices, policies and goals.
- C. The undersigned bidder/contractor/supplier/vendor understands and agrees: to submit to the park district upon request statistical data concerning employee composition or membership composition by race, color, sex, age, disability and job description.
- D. The undersigned bidder/contractor/supplier/vendor understands and agrees: to distribute copies of the above commitment (A) to all persons who participate in recruitment, screening, referral and selection of job applicants and prospective job applicants or members.
- E. The undersigned bidder/contractor/supplier/vendor understands and agrees: to require any subcontractor to submit to the District a written commitment with who he/she contracts with in the amount of \$5,000.00/Sub-Contract or \$1,000.00/Supplier/Vendor (per purchase or in accumulated amount in any fiscal year of the District) or more to engage in Affirmative Action practices.

I certify that I have answered all the foregoing questions and provided all the foregoing information correctly and truthfully to the best of my knowledge and ability.

Signature of Authorized Agent

Date

Title

Telephone Number

All information provided the Champaign Park District will be held in strictest confidence.

SECTION VI: AFFIRMATIVE ACTION CONTRACTOR'S COMPLIANCE REPORT

Part I: Identification

1. Company's main office address: _____

Telephone: _____ Fax: _____
Federal employer's identification number: _____
2. In what capacity would the company do business with the Park District?
☐ Contractor ☐ Sub-contractor ☐ Vendor ☐ Supplier ☐ Other _____
3. Major activity of company (principle product or service). _____

4. Is the company presently pre-qualified to do business with the Park District or other local and/or state government?
☐ Yes ☐ No *If yes with what agency(ies)?* _____
- During the last 12 months has the company performed business with any governmental agency federal, state, county, municipal, school districts, etc.)?
☐ Yes ☐ No *If yes with what agency(ies)?* _____

Part II: Policies and Practices

- A. Is the company's policy to recruit, hire, train, upgrade, promote and discipline persons without regard to race, color, religion, sex, national origin or ancestry, age or disability? ☐ Yes ☐ No
- B. Has the company developed a written affirmative action policy?
☐ Yes ☐ No *If yes, a copy of the policy shall be provided to the District upon request.*
- C. Does the company have an affirmative action officer or person responsible for affirmative action?
☐ Yes *If yes please complete.* ☐ No
Name: _____
Title: _____
Telephone: _____
- C. Does the company have bargaining agreements with employee organizations?
☐ Yes ☐ No
If yes, have such organizations been notified of the company's responsibility to comply with the Champaign Park District's affirmative action program? ☐ Yes ☐ No

Champaign Park District: Invitation for Bids Sholem Concrete Repairs and Epoxy

Comments: _____

SECTION VI: AFFIRMATIVE ACTION CONTRACTOR'S COMPLIANCE REPORT (CONTINUED)

- E. Has the company notified all of its sub-contractors of their obligations to comply with the Champaign Park District's affirmative action program? ☐ Yes ☐ No

Comments: _____

Part III: Personnel Inventory

Occupations	White		Black		Hispanic		Other	
	Male	Female	Male	Female	Male	Female	Male	Female
Officials & Managers								
Professionals								
Technical								
Sales Workers								
Office & Clerical								
Crafts (skilled)								
Operatives (semi-skilled)								
Laborers (unskilled)								
Service Workers								
Apprentices (blue collar)								
On the job trainees (blue collar)								
On the job trainees (white collar)								
Totals								

The undersigned bidder/contractor/vendor/supplier has analyzed the workforce and submits the following workforce figures. The Champaign Park District will hold all information in the strictest confidence.

Above employee figures were obtained from: ☐ Visual check ☐ Employment records

Signature of Authorized Agent

Date

Title

Telephone Number

CHAMPAIGN PARK DISTRICT CONTRACTOR AGREEMENT

This Agreement (hereafter called, "Agreement") made and effective as of _____, 2025 by and between the CHAMPAIGN PARK DISTRICT, a municipal corporation of the State of Illinois, located at 706 Kenwood Road, Champaign, IL 61821 (hereafter referred to as, "Owner"), and _____, a _____ corporation (hereafter referred to as, ("Contractor")), located at _____, and individually or collectively referred to as "Party" or "Parties", as the case may be.

TERMS AND CONDITIONS

Owner and Contractor desire to enter into this Agreement, pursuant to which Contractor shall perform certain construction work and other duties in strict accordance with the following terms and conditions (collectively the "Work"), and, subject to the terms and conditions of this Agreement, the Owner shall pay for such performance of the Work. In consideration of these terms and conditions and other good and valuable consideration, the receipt of which is hereby acknowledged and intending to be legally bound, the Parties agree as follows:

1. **Project.** Contractor shall perform all Work required for installing new epoxy coatings and concrete repairs at Sholem Aquatic Center, located at 2205 Sangamon Dr, Champaign, Illinois (the "Project"). Contractor shall undertake the Project and perform all Work and other duties in strict accordance with the "Contract Documents," which consist of this Agreement, the Scope of Work, and Specifications attached to this Agreement as Exhibit A.

2. **Contractor's Performance.** Contractor shall perform all Work utilizing the highest standards of workmanship and materials. Contractor shall maintain a sufficient staff to perform all Work in the most expeditious manner consistent with the interests of Owner. Contractor shall promptly notify Owner immediately in writing: (i) of any information required from Owner and necessary for Contractor to complete its Work in a timely manner; and (ii) of any Work requested by Owner that is not included in the scope of Work provided in the Contract Documents. Contractor shall be solely responsible for means and methods selected in performing the Work. Contractor shall supervise all Work so that it is performed in a safe and expeditious manner. Contractor shall be solely responsible for the Work of its employees and its subcontractors' and suppliers' employees.

a. Contractor shall carry the Work forward regularly, diligently, uninterruptedly and expeditiously at such a rate of progress and with an adequate work force as shall ensure the completion of the Work in accordance with the Contract Documents by the Final Completion date. It is expressly understood and agreed by and between Contractor and Owner that the time for completion of the Work is a reasonable time, taking into consideration the average climatic range, usual industrial conditions, and all other conditions and actors prevailing in this locality. Contractor shall promptly notify the Owner immediately in writing: (i) of any information required from the Owner and necessary for Contractor to complete its Work in a timely manner; and (ii) of any Work requested by the Owner or required for the Project that is not included in the scope of Work reflected in the Contract Documents. Contractor shall be solely responsible for means and methods selected in performing the Work. Contractor shall supervise all Work so that it is performed in a safe manner. Contractor shall be solely responsible for the Work of its employees and its subcontractors' and suppliers' employees. Contractor shall keep all documents and information related to the Project confidential and, except as required by law, shall not disclose such documents or information to any person or other party except the employees of Contractor and its subcontractors who need such documents or information to perform the Work and complete the Project.

b. Contractor shall confine all equipment, the storage of materials and the operations of its workers, to limits indicated by law, ordinances, permits, or directions of the Owner and shall not unreasonably encumber the Project site with such materials. The Project site shall not be utilized for the storage of vehicles, materials, equipment, or fixtures not intended for the Work to be performed.

c. Contractor shall notify all utility companies, public and private, as necessary in advance of commencing performance of the Work. The responsibility for moving water lines, gas lines, wire lines, service connections, water and gas meter boxes, water and gas valve boxes, light standards, cable ways, signals and all other utility appurtenances which are within the limits of the proposed construction shall be assumed by the Contractor, at no additional compensation. The Contractor shall verify the location of all utilities prior to the start of construction

Champaign Park District: Invitation for Bids Sholem Concrete Repairs and Epoxy

and shall be responsible for the preservation of existing utility installation and the cost of providing precautionary supports, braces, or other equipment to insure against damage to said utility installation. The cost to repair and replace any new or existing utilities damaged shall be paid for by the Contractor.

d. If Contractor uncovers or discovers any concealed condition differing materially from conditions depicted in the Contract Documents or differing from conditions reasonably anticipated or inherent in the Work, Contractor shall immediately stop the Work and notify the Owner of the condition in writing. The Owner shall then issue written directions. Contractor shall not proceed with the Work until the Owner has issued written directions. The contract time and Contract Sum shall be equitably adjusted if necessitated by such directions of the Owner.

e. Contractor acknowledges and agrees that neither Contractor nor anyone with whom it may hire as an employee or independent contractor is an employee of the Owner, and are not entitled to any benefits or protections afforded employees of the Owner, nor controlled as employees of the Owner. Nevertheless, Contractor, its employees and independent contractors shall not act contrary to the policies of the Owner. Contractor understands and agrees that Contractor shall not be insured under provisions of the unemployment compensation insurance of the Owner or the workers' compensation insurance of the Owner, and that any injury or property damage in connection with the work performed shall be Contractor's sole responsibility and not that of the Owner. It is also understood that Contractor is not protected as an employee or as a person acting as an agent or employee under the provisions of the general liability insurance of the Owner and, therefore, Contractor shall be solely responsible for Contractor's own acts or omissions, and those of Contractor's employees, contractors, and agents, if any. The Owner shall not in any manner whatsoever be obligated to defend, indemnify or hold harmless Contractor, or Contractor's employees and agents, if any, in matters of liability.

f. Contractor acknowledges and agrees that Contractor is solely responsible to pay all applicable federal, state and local income and withholding tax obligations or contributions imposed pursuant to Social Security, unemployment insurance and worker's compensation insurance on behalf of Contractor and those employees, contractors, and agents, if any, employed by Contractor.

3. **Correction of Work.** If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents or fails within a seven (7) day period after receipt of written notice from the Owner to commence and continue correction of such default or neglect with diligence and promptness, the Owner may, without prejudice to other remedies, correct such deficiencies. If the Contractor fails to correct nonconforming Work within a reasonable time as determined in the sole reasonable discretion of Owner, the Owner may correct it as provided for herein.

4. **Substantial Completion.** Contractor shall cause all Work required by the Contract Documents to be substantially completed by November 20th, 2026 ("Substantial Completion"). "Substantial Completion" means that the Owner can occupy and fully utilize the completed Project for its intended use, and that all warranties, manuals, instructions, certifications, reports, record or as-built drawings, and any other document required by the Contract Documents have been properly submitted to and accepted by the Owner; and that the only remaining Work is minor cosmetic work that does not interfere with the Owner's operations (the "Punch List Work"). The Contractor shall complete the Punch List Work within ten (10) days after the date of Substantial Completion. Time is of the essence under this Agreement.

5. **Materials.** All materials incorporated into the Work shall be new and of high quality. Contractor shall follow all manufacturer's instructions and recommendations. If requested by Owner or otherwise required by the Contract Documents, Contractor shall, before purchase of such material, submit to Owner for Owner's review, and in a format acceptable to Owner, all product data, literature, and shop drawings.

6. **Differing Site Conditions.** If Contractor uncovers or discovers any concealed condition differing materially from conditions depicted in the Contract Documents or differing from conditions reasonably anticipated or inherent in the Work, Contractor shall immediately stop the Work and notify the Owner of the condition in writing. The Owner shall then issue directions. The contract time and contract price may be equitably adjusted if necessitated by such directions of the Owner. However, prompt written notice by the Contractor of the condition, followed by written directions from the Owner, shall be conditions precedent to such adjustments.

Champaign Park District: Invitations for Bids for Sholem Concrete Repairs and Epoxy

7. **Changes in the Work.** The Owner, without invalidating the Contract, may order changes in the Work within the general scope of the Contract, consisting of additions, deletions, or other revisions, and the Contract Sum and Contract Time shall be adjusted accordingly, in writing. If the Owner and Contractor cannot agree to a change in the Contract Sum, the Owner shall pay the Contractor its actual cost plus reasonable overhead and profit. If concealed or unknown physical conditions are encountered at the site that differ materially from those indicated in the Contract Documents or from those conditions ordinarily found to exist, the Contract Sum and Contract Time shall be subject to equitable adjustment.

8. **Contractor's Compensation.** Owner shall pay Contractor the sum of **INSERT AMOUNT OF CONTRACT** for Work properly performed under this Agreement. In the event conditions arise which Contractor believe warrant a change in compensation, Contractor shall notify Owner of such conditions in writing to request approval of additional compensation. Contractor shall not be entitled to any additional compensation unless previously approved by Owner in writing.

9. **Payments to the Contractor.** On a monthly basis during the progress of the Work, Contractor shall, by such day as the Owner may specify, submit monthly payment applications to the Owner reflecting on an itemized percentage basis of the Contract Sum the value of all Work completed in the previous month. Owner shall pay properly submitted pay applications within thirty (30) days after receipt. Such payments shall be made as a percentage of the Contract Sum which is equal to the percentage of completion of the Work, less retention of ten percent (10%). When the Work is fifty percent (50%) complete, the retention held by Owner shall be five percent (5%) until final completion of the Project, including the completion of all Punch List Work. Each monthly pay application shall be accompanied by lien waivers covering all lien rights, including lien rights related to the then-current pay period, and all lien rights arising from payments previously made by Owner. Owner may elect to receive from Contractor trailing lien waivers from Contractor's subcontractors. At least once per month or as otherwise required prior to final completion of the Work, the Contractor and each subcontractor shall submit to the Illinois Department of Labor certified payrolls in accordance with Section 5 of the Illinois Prevailing Wage Act, 820 ILCS 130/5.

In the event the contract work has been awarded on a unit price bid basis, the form of each application shall follow the Bid Proposal Form, listing each item number, the total quantity of units completed to date of the estimate, the unit price and subtotal. The subtotal column shall be added to show the total cost of work completed to date, less ten (10%) percent to be withheld until the Contract is fifty percent (50%) complete, giving the total amount requested for payment. Until the Contract is fifty percent (50%) complete, previous applications for payment paid by the Owner shall be shown on each subsequent request and subtracted after the ten percent (10%) has been withheld.

After fifty percent (50%) of the Contract is complete, the subtotal column shall be added to show the total cost of work completed to date, less five percent (5%) to be withheld, giving the total amount requested for payment. After the Contract is fifty percent (50%) complete, previous applications for payment paid by the Owner shall be shown on each subsequent request and subtracted after the five percent (5%) has been withheld.

When issuing payment, Contractor and all subcontractors shall comply with the retainage limits as set forth in the Public Construction Bond Act, 30 ILCS 550/1 et seq.

In the event of any past due payment by Owner, such payment shall not bear interest in excess of the rate of twelve percent (12%) per annum pursuant to the Illinois Local Government Prompt Payment Act and this provision shall control regardless of any amendment, addendum, or exhibit to this Agreement.

10. **Defective Work and Guarantee.** All Work shall be of high quality and free of defect. Contractor shall promptly correct any defective Work. Payment by Owner for any Work later determined to be defective shall not relieve Contractor of its obligation to correct defective Work. Contractor hereby warrants that all Work is and shall remain free from defect for two (2) years following Substantial Completion, and upon notice by the Owner, Contractor shall promptly correct such defects appearing within such two (2) year period. This warranty is in addition to any warranties that may be required by the Contract Documents, statutes of limitation under applicable law, and this warranty does not abrogate or nullify any breach of contract claim or other causes of action Owner may have against Contractor.

Champaign Park District: Invitation for Bids Sholem Concrete Repairs and Epoxy

11. **Default.** In the event that either Party fails to comply with the terms of this Agreement, and cure such default within _____ (____) days' written notice from the other Party, then the non-defaulting Party shall have the right to terminate this Agreement. Subject to section 12, any such termination shall not terminate or affect the obligations or rights to enforce the same as they may have accrued prior to termination which shall survive such termination.

12. **Termination.** The Owner may terminate this Agreement at any time for convenience and without cause by written notice to the Contractor and the Owner shall pay the Contractor for Work properly completed to the date of termination. This Agreement may be terminated at any time by mutual agreement of the Parties and the Owner shall pay the Contractor for Work properly completed to the date of termination. This Agreement may be terminated by either Party for "cause" by giving _____ (____) days' notice to the other Party in writing of such termination. For the purposes of this Agreement, "termination for cause" is defined as termination for breach or an intentional or willful violation of any of the provisions of this Agreement by a Party. The Party terminating this Agreement for cause shall specify in such writing the nature of the "cause" resulting in termination. In the event of termination for cause, Owner shall have no further obligation other than to make payments to Contractor for Work completed satisfactorily, and Contractor shall be liable to Owner for any increase in cost incurred by Owner in completing the Work. Regardless of whether Owner exercises its right to termination, Contractor hereby waives any and all claims for lost profits, and any for any other consequential or incidental damages arising because of a termination.

13. **Prevailing Wage Act.** The Contractor shall pay prevailing wages in accordance with and shall fully comply with all requirements of the Prevailing Wage Act, 820 ILCS 130/0.01, *et seq.* This Agreement calls for the construction of a "public work," within the meaning of the Illinois Prevailing Wage Act, 820 ILCS 130/.01 *et seq.* ("the Act"). The Act requires contractors and subcontractors to pay laborers, workers and mechanics performing services on public works projects no less than the current "prevailing rate of wages" (hourly cash wages plus amount for fringe benefits) in the county where the work is performed. The Department publishes the prevailing wage rates on its website at <http://labor.illinois.gov/>. The Department revises the prevailing wage rates and the contractor/subcontractor has an obligation to check the Department's website for revisions to prevailing wage rates. For information regarding current prevailing wage rates, the Illinois Department of Labor's website is to be examined. All Contractors, subcontractors, and sub-subcontractors rendering services under this Agreement must comply with all requirements of the Act, including but not limited to, all wage requirements, notice, and record keeping duties.

14. **Person and Property Protection.** The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs, including all those required by law in connection with performance of the Contract. The Contractor shall take reasonable precautions to prevent damage, injury, or loss to employees on the Work and other persons who may be affected thereby, the Work and materials and equipment to be incorporated therein, and other property at the site or adjacent thereto. The Contractor shall promptly remedy damage and loss to property caused in whole or in part by the Contractor, or by anyone for whose acts the Contractor may be liable.

15. **Liens.** If any liens or claims of lien are placed on the Work, property of Owner, or the funds designated for the Project, and such liens or claims of lien are due to Contractor's breach of this Agreement or other circumstances or events under Contractor's control, Contractor shall indemnify Owner for all costs, expenses, and attorneys' fees incurred in the resolution of such lien, and Owner shall have the right to withhold from payments due to the Contractor an amount sufficient to satisfy such lien or claim of lien, along with an amount sufficient to cover attorneys' fees and other costs and expenses that have been or may be incurred by Owner in connection with the resolution of such lien or claim of lien.

16. **Insurance.** Contractor shall keep in full force and effect at all times during this Agreement a comprehensive general liability insurance policy, with contractual liability coverage, with minimum limits of not less than \$1,000,000 per occurrence and \$2,000,000 annual aggregate together with property damage insurance of not less than \$1,000,000. All insurance carriers providing the coverage set forth herein shall have a rating of A as assigned by A.M. Best and Co. and shall be reasonably satisfactory to Owner. All insurance coverage provided by Contractor shall be primary insurance as to Owner. Any insurance or self-insurance maintained by Owner shall be in excess of Contractor's insurance and shall not contribute with it. The Owner, its commissioners, officers,

Champaign Park District: Invitations for Bids for Sholem Concrete Repairs and Epoxy

employees, agents, representatives, and volunteers shall be covered as additional insured's under the general liability coverage which shall contain no special limitation on the scope of protection afforded to the additional insured's, and shall contain appropriate endorsements, extensions or riders necessary to assure coverage, together with such certificates of insurance which identify the required coverages. All liability insurance shall provide coverage on an "occurrence" basis and not on a "claims made" basis. Such policies shall not be cancelled or amended without at least ten (10) days prior written notice having been given to the Owner. Cancellation of any such coverage without a substitute policy containing the required coverage's being put in force, shall be grounds for the Owner to immediately terminate this Agreement with no further rights afforded Contractor. At its option, Owner may continue such insurance at its cost and obtain reimbursement and repayment thereof from Contractor. In such event, Contractor shall pay the amount due within ten (10) days of payment by Owner. The Parties acknowledge that Contractor may from time to time change insurers; provided that, the Owner shall be provided with a certificate of such insurance otherwise conforming to and in compliance with the terms hereof, promptly upon such change. Contractor shall maintain worker's compensation insurance sufficient to satisfy all applicable state and/or federal laws and must show policy number on certificate of insurance if workman's compensation is provided. Contractor shall keep comprehensive automobile liability insurance with a bodily injury limit of \$1,000,000 per person and \$1,000,000 per accident. Such automobile liability insurance shall cover property damage of \$500,000 each occurrence or combined single limit of \$500,000. Contractor shall carry umbrella liability insurance with minimum limits of \$5,000,000 in the aggregate.

17. **Performance and Payment Bond.** If the contract amount is in excess of \$50,000, prior to performing the Work, Contractor shall provide the Owner with a Performance Bond and a Labor/Material Payment Bond in a form acceptable to the Owner for the full amount of the contract price.

18. **Indemnification.** Contractor shall indemnify, defend, and hold harmless Owner, its commissioners, directors, officers, employees, agents, representatives, and volunteers from any and all claims, demands, causes of action, losses, liens, claims of lien, liabilities, penalties, and damages, including reasonable attorneys' fees and court costs, to the extent arising from any negligent act or omission of Contractor, its employees, or its subcontractors, suppliers, and their employees, and to the extent arising from any breach of this Agreement by Contractor. The Contractor hereby knowingly and intentionally waives the right to assert, under the case of *Kotecki v. Cyclops Welding Corp.*, 146 Ill.2d 155 (1991) that Contractor's liability may be limited to the amount of its statutory liability under the Workers' Compensation Act, and agrees that Contractor's liability to indemnify and defend the Owner and Architect is not limited by the so called "Kotecki Cap". The Contractor shall include this provision in each of its subcontract agreements and shall require its subcontractors to be so bound. Owner shall not be obligated in any manner whatsoever to pay or reimburse Contractor's attorneys' fees and expenses and this provision shall control regardless of any amendment, addendum, or exhibit to this Agreement.

19. **Successors and Assigns.** Contractor shall not assign any rights, delegate, or subcontract any obligations or duties under this Agreement without the prior written consent of the Owner, and any attempted assignment, delegation or subcontracting without such consent shall be void. This Agreement shall be binding upon and inure to the benefit of the Parties hereto and their respective permitted successors and assigns.

20. **Applicable Law and Venue.** This Agreement is governed by and shall be interpreted according to the laws of the State of Illinois, without application of its conflict of laws provisions. Each Party has reviewed and approved this Agreement and the rule of construction that resolves ambiguities against the drafting party shall not be employed in the interpretation of this Agreement. In the event of any claims or lawsuits regarding this Agreement, a state or federal court located in Champaign County, Illinois, shall be the venue for such claims or suits.

21. **Severability.** In the event any one or more of the provisions set forth in this Agreement shall be invalid, illegal, or unenforceable in any respect, such provision shall be deemed severed from this Agreement, and the validity, legality, or enforceability of the remaining provisions of this Agreement or any other application thereof shall not be affected or impaired thereby, and shall, therefore, remain in effect.

22. **Waiver.** Failure to insist upon strict compliance with any of the terms, covenants, or conditions of this Agreement, shall not be deemed a waiver of that term, covenant, or condition, nor shall any waiver or relinquishment of any right or power at any one time or times be deemed a waiver or relinquishment of the right or

Champaign Park District: Invitation for Bids Sholem Concrete Repairs and Epoxy

power at all or any other times.

23. **Counterparts.** This Agreement may be executed in any number of counterparts as may be convenient or required for the benefit of the Parties. It shall not be necessary that the signature of, or on behalf of, each Party, or that the signature of all persons required to bind any Party, appear on each counterpart. All counterparts shall collectively constitute a single instrument. It shall not be necessary in making proof of this instrument to produce or account for more than a single counterpart containing the respective signatures of, or on behalf of, each of the Parties hereto. Any signature page to any counterpart may be detached from any such counterpart without impairing the legal effect of the signatures thereon and thereafter attached to another counterpart identical thereto, except having attached to it additional signature pages.

24. **Digital Transmissions.** The Parties agree that each may rely, without investigation, upon the genuineness and authenticity of any document, including any signature or purported signature, transmitted digitally, without reviewing or requiring receipt of the original document. Each document or signature so transmitted shall be deemed an enforceable original. Upon request, the transmitting Party agrees to provide the receiving Party with the original document transmitted digitally; however, the Parties agree that the failure of either Party to comply with such a request shall in no manner whatsoever affect the genuineness, authenticity, or enforceability of the document or this contract. Each Party waives and relinquishes as a defense to the formation or enforceability of any contract between the Parties, or provision thereof, the fact that a digital transmission was utilized.

25. **Notice.** All notices required pursuant to this Agreement shall be in writing, and shall be deemed to have been given at the time they are mailed to the respective Party via certified mail, return receipt requested with an additional copy sent via U.S. first class mail at the address set forth below, or at such other place or address as the Parties shall provide to each other in writing.

Champaign Park District
Attn: Executive Director
706 Kenwood Road
Champaign, IL 61821

26. **Force Majeure.** The Parties shall not be liable for, nor shall either of them be considered in breach of this Agreement due to, in whole or in part, any delay, failure or inability to perform the Services or other obligations under this Agreement as a result of a cause beyond its reasonable control, including, without limitation, any act of God or a public enemy or terrorist; any act, omission, or delay in action of any military, governmental, quasi-governmental, or regulatory authority or agency; any local, state, regional, or federal emergency; change in any law, rule, or regulation; any natural disaster or other like event; any epidemic or pandemic; any quarantine, self-quarantine, shelter-in-place, or like preventive measure issued or recommended by any governmental or quasi-governmental authority or agency; or any disruption or outage of communications, power or other utility. The time for performance required of the Parties (to the extent such delay, failure, or inability is reasonably curable by additional time) shall be extended by the period of such delay and in no event shall a Party be expected to expend or incur any additional costs or expenses beyond those reasonably anticipated at the commencement of this Agreement, nor shall the occurrence of the Force Majeure Event affect the obligation of a Party to pay money (or cause any third party to make payment of money on a Party's behalf) in a timely manner which matured prior to the occurrence of Force Majeure Event.

In the event the Work is delayed due to a cause beyond the reasonable control of Contractor, including strikes, labor disputes, lockouts, fire, shortages of labor or material, inclemency of weather, accidents, casualties, pandemic outbreaks, or government orders, Contractor shall not be liable for any damages caused by such delays, shortages, or disruptions and, provided that Contractor is in compliance with all other relevant provisions of this Agreement, the contract time shall be extended for such reasonable time as the Owner may determine; provided that, such extension of contract time shall be net of any delays caused by or due to the fault or negligence of Contractor or which are otherwise the responsibility of Contractor and shall also be net of any contingency or "float" time allowance included in Contractor's construction schedule. Contractor shall, in the event of any occurrence likely to cause a delay, cooperate in good faith with the Owner to minimize and mitigate the impact of any such occurrence

Champaign Park District: Invitations for Bids for Sholem Concrete Repairs and Epoxy

and do all things reasonable under the circumstances to achieve this goal. Any such extension of contract time pursuant to this section shall be reduced to a Change Order. Extension of contract time pursuant to this section shall be the Contractor's sole and exclusive remedy for delay.

27. **Representation of Authority.** Each person executing this Agreement represents that they are authorized to execute the Agreement. Each person executing this Agreement on behalf of any entity represents that they are authorized to execute this Agreement on behalf of such entity.

28. **Entire Agreement.** This Agreement and the Contract Documents and any exhibits or amendments represent the entire agreement between Contractor and Owner with respect to this Project, and supersede all prior representations, negotiations or agreements, written or oral, which are not included herein. This Agreement may only be amended by written instrument executed by Owner and Contractor. In the event of a conflict between this Agreement and the Contract Documents, this Agreement shall control.

29. **Time of the Essence.** Time is of the essence of this Agreement. It shall be binding upon the representatives, successors and permitted assigns of the Parties hereto.

WHEREOF, the Parties hereto have caused this Agreement to be executed and effective as of the date first above written.

**Champaign Park District,
a municipal corporation**

[CONTRACTOR]


By: _____

By: _____

Its: _____

Its: _____

EXHIBIT A – SCOPE OF WORK



POOL COATINGS

HIGH-PERFORMANCE PROTECTION

MUNICIPAL POOLS, NATATORIUMS, UNIVERSITY POOLS,
NEIGHBORHOOD POOLS, APARTMENT POOLS, WATER PARKS

Every pool faces the same challenges. High maintenance costs put financial restrictions on parks and recreation departments, schools, pool management companies, builders, homeowner associations and taxpayers. The lack of proper coating protection puts the pool – a major investment – at risk. And if its painted interior face is cracked, faded, stained, slick or algae-covered, the pool just isn't very inviting.

Abrasion, chlorine contact, constant immersion, and exterior exposure will take their toll on all pool paints. Many will crack, peel, blister and chip after as little as one season, causing the very maintenance problems you're trying to solve.

Tnemec's high-build epoxy finishes tenaciously adhere to the substrate to resist moisture, abrasion, chemical attack and extreme seasonal temperatures.


FEATURES AND BENEFITS

- Low temperature cure available – will cure in temperatures as low as 35°F (2°C)
- Versatile application – spray, brush or roll
- VOC-compliant versions for all air districts
- Available in standard and accent colors
- Low cost installed coating systems
- A single source for all your coating needs


Tnemec's epoxy technology puts history and experience on your side. It has been the benchmark immersion coating for drinking water storage tanks and water treatment equipment for years. And there are decades of proven performance on pools, indoors and out.

Your Tnemec representative offers excellent technical knowledge, assists with specifications and provides product recommendations to help applicators achieve optimal results. To get started, contact your local Tnemec representative.


STANDARD COLORS



P001 Tnemec White-Pool



P002 Tank White-Pool



P003 Star-Pool



P004 Clear Sky-Pool*




P005 Fountainbleu-Pool



P006 Delft Blue-Pool



P007 Light Gray-Pool*




P008 Cumulus-Pool



P009 Mineral Water-Pool*

ACCENT COLORS



P020 Black-Pool*



P021 True Blue/Safety-Pool*



P276 Safety Red-Pool*

NOTE: Colors represented are digital reproductions of actual standards and will vary in appearance due to differences in monitor and video card output. These digital representations should not be used to finalize color selection(s). Please contact your Tnemec representative for color-accurate samples or for assistance with suitable primer and finish coat selections and color matching.

**Color only available in Series N69, N69F, L69, or L69F.*

Additional colors are available. Contact your Tnemec representative for more information.

CONTACT

Published technical data, instructions and pricing are subject to change without notice. Contact your Tnemec technical representative for current technical data, instructions and pricing. Warranty information: The service life of Tnemec's coatings will vary. For warranty, limitation of seller's liability and product information, please refer to Tnemec Product Data Sheets at tnemec.com or contact your Tnemec technical representative. © Tnemec Company, Inc. 2023 FLYPOOL



HI-BUILD EPOXOLINE® II SERIES N69F

PRODUCT PROFILE

GENERIC DESCRIPTION	Polyamidoamine Epoxy
COMMON USAGE	An advanced generation epoxy for the protection and finishing of steel and concrete. It has excellent resistance to abrasion and is suitable for immersion as well as chemical contact exposure. Contact your local Tnemec representative for a list of chemicals. This product can also be used as a block filler on cementitious or masonry substrates.
COLORS	Refer to Tnemec Color Guide. Note: Epoxies chalk with extended exposure to sunlight. Lack of ventilation, incomplete mixing, miscatalyzation or the use of heaters that emit carbon dioxide and carbon monoxide during application and initial stages of curing may cause yellowing to occur.
FINISH	Satin

COATING SYSTEM

SURFACER/FILLER/PATCHER	Series 215, 217, 218
PRIMERS	Steel: Self-priming or Series 1, 27, 37H, 66, L69, L69F, N69, V69, 90E-92, 90G-1K97, 90-97, H90-97, 90-98, 91-H ₂ O, 94-H ₂ O, 135, 161, 394 Galvanized Steel and Non-Ferrous Metal: Self-priming or Series 66, L69, L69F, N69, V69, 161 Concrete: Self-priming or Series 130, 1254 CMU: Self-priming or Series 130, 1254
TOPCOATS	Series 21, 22, 46H-413, 66, L69, L69F, N69, N69F, V69, V69F, 73, 104, 113, 114, 118, 141, 156, 157, 161, 180, 181, 287, 435, 436, 1026, 1028, 1029, 1070, 1070V, 1071, 1071V, 1072, 1072V, 1077, 1078, 1078V, 1080, 1081, 1094, 1095, 1096, 1224. Note: The following recoat times apply for Series N69F: Immersion Service—Surface must be scarified after 30 days. Atmospheric Service—After 30 days, scarification or an epoxy tie-coat is required. Contact your Tnemec representative for specific recommendations.

SURFACE PREPARATION

STEEL	Immersion Service: SSPC-SP10/NACE 2 Near-White Blast Cleaning or ISO Sa 2 1/2 Very Thorough Blast Cleaning with a minimum angular anchor profile of 1.5 mils. Non-Immersion Service: SSPC-SP6/NACE 3 Commercial Blast Cleaning or ISO Sa 2 Thorough Blast Cleaning with a minimum angular anchor profile of 1.5 mils. Note: Commercial Blast Cleaning generally produces the best coating performance for this exposure. If conditions will not permit this, in moderate exposures Series N69F may be applied to SSPC-SP2 or SP3 Hand or Power Tool Cleaned surfaces (SSPC Rust Grade Condition C).
GALVANIZED STEEL & NON-FERROUS METAL	Surface preparation recommendations will vary depending on substrate and exposure conditions. Contact your Tnemec representative or Tnemec Technical Services.
CAST/DUCTILE IRON	All external surfaces of ductile iron pipe and fittings shall be delivered to the application facility without asphalt or any other protective lining on the exterior surface. All oils, small deposits of asphalt paint, grease, and soluble deposits should be removed and uniformly abrasive blasted using angular abrasive in accordance with NAPF 500-03-04: External Pipe Surface condition. When viewed without magnification, the exterior surfaces shall be free of all visible dirt, dust, loose annealing oxide, rust, mold coating and other foreign matter. Any area where rust reappears before application shall be reblasted. The surface shall contain a minimum angular anchor profile of 1.5 mils (38.1 microns) (Reference NACE RP0287 or ASTM D 4417, Method C).
CONCRETE	Allow new cast-in-place concrete to cure a minimum of 28 days at 75°F (24°C). Verify concrete dryness in accordance with ASTM F 1869 "Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride" (moisture vapor transmission should not exceed three pounds per 1,000 square feet in a 24 hour period), F 2170 "Standard Test Method for Determining Relative Humidity in Concrete using in situ Probes" (relative humidity should not exceed 80%), or D 4263 "Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method" (no moisture present). Prepare concrete surfaces in accordance with NACE No. 6/SSPC-SP13 Joint Surface Preparation Standards and ICRI Technical Guidelines. Abrasive blast, shot-blast, water jet or mechanically abrade concrete surfaces to remove laitance, curing compounds, hardeners, sealers and other contaminants and to provide an ICRI-CSP 2-3 surface profile. Large cracks, voids and other surface imperfections should be filled with a recommended filler or surfacer.
CMU	Allow mortar to cure for 28 days. Level protrusions and mortar spatter.
PAINTED SURFACES	Non-Immersion Service: Ask your Tnemec representative for specific recommendations.
PRIMED SURFACES	Immersion Service: Scarify the Series N69F prime coat surface by abrasive-blasting with a fine abrasive before topcoating if: (a) the Series N69F prime coat has been in exterior exposure for seven (7) days or longer and Series 435 is the specified topcoat; (b) the Series N69 prime coat has been in exterior exposure for 60 days or longer and Series 66, L69, L69F, N69, N69F, V69, V69F or 161 is the specified topcoat.
ALL SURFACES	Must be clean, dry and free of oil, grease, chalk and other contaminants.

TECHNICAL DATA

VOLUME SOLIDS	69.0 ± 2.0% (mixed) †
RECOMMENDED DFT	2.0 to 10.0 mils (50 to 255 microns) per coat. Note: The number of coats and thickness requirements will vary with substrate, application method and exposure. Contact your Tnemec representative.

HI-BUILD EPOXOLINE® II | SERIES N69F

CURING TIME AT 5 MILS DFT

Temperature	To Handle	To Recoat	Immersion
75°F (24°C)	4 hours	5 hours	3 days
65°F (18°C)	7-8 hours	9-11 hours	8 days
55°F (13°C)	12-14 hours	16-20 hours	9-10 days
45°F (7°C)	18-22 hours	28-32 hours	12-13 days
35°F (2°C)	28-32 hours	46-50 hours	16-18 days

Curing time varies with surface temperature, air movement, humidity and film thickness.

VOLATILE ORGANIC COMPOUNDS

Unthinned: 2.30 lbs/gallon (280 grams/litre)
Thinned 10% (No. 4 Thinner): 2.75 lbs/gallon (330 grams/litre)
Thinned 10% (No. 60 Thinner): 2.76 lbs/gallon (331 grams/litre)

HAPS

Unthinned: 2.35 lbs/gal solids
Thinned 10% (No. 4 Thinner): 3.20 lbs/gal solids
Thinned 10% (No. 60 Thinner): 2.35 lbs/gal solids

THEORETICAL COVERAGE

1,107 mil sq ft/gal (27.2 m²/L at 25 microns). See APPLICATION for coverage rates. †

NUMBER OF COMPONENTS

Two: Part A (amine) and Part B (epoxy) — One (Part A) to one (Part B) by volume.

PACKAGING

	Part A	Part B	Yield (mixed)
Large Kit	5 gallon pail	5 gallon pail	10 gallons (37.9 L)
Small Kit	1 gallon can	1 gallon can	2 gallons (7.6 L)

NET WEIGHT PER GALLON

13.34 ± 0.25 lbs (6.10 ± 0.11 kg) (mixed)

STORAGE TEMPERATURE

Minimum 20°F (-7°C) Maximum 110°F (43°C)

TEMPERATURE RESISTANCE

(Dry) Continuous 250°F (121°C) Intermittent 275°F (135°C)

SHELF LIFE

Part A: 24 months; Part B: 12 months at recommended storage temperature.

FLASH POINT - SETA

Part A: 82°F (28°C) Part B: 93°F (34°C)

HEALTH & SAFETY

Paint products contain chemical ingredients which are considered hazardous. Read container label warning and Material Safety Data Sheet for important health and safety information prior to the use of this product.
Keep out of the reach of children.

APPLICATION

COVERAGE RATES

	Dry MILS (Microns)	Wet MILS (Microns)	Sq Ft/Gal (m ² /Gal)
Suggested (1)	6.0 (150)	9.0 (230)	184 (17.1)
Minimum	2.0 (50)	3.0 (75)	553 (51.4)
Maximum	10.0 (250)	15.0 (375)	111 (10.3)

Dense Concrete & Masonry: From 100 to 150 sq ft (9.3 to 13.9 m²) per gallon.

CMU: From 75 to 100 sq ft (7.0 to 9.3 m²) per gallon.

(1) Note for Steel: Roller or brush application requires two or more coats to obtain recommended film thickness. Also, Series N69F can be spray applied to an optional high-build film thickness range of 8.0 to 10.0 dry mils (205 to 255 dry microns) or 11.5 to 14.5 wet mils (209 to 370 wet microns). Allow for overspray and surface irregularities. Film thickness is rounded to the nearest 0.5 mil or 5 microns. Application of coating below minimum or above maximum recommended dry film thicknesses may adversely affect coating performance. †

MIXING

Start with equal amounts of Series N69F Parts A and B. Power mix contents of each container separately, making sure no pigment remains on the bottom. Pour a measured amount of Part B into a clean container large enough to hold both components. Add an equal volume of Part A to Part B while under agitation. Continue agitation until the two components are thoroughly mixed. **Note:** Both components must be above 50°F (10°C) prior to mixing. For optimum mixing and application properties, the material should be above 60°F (16°C).

Thin by volume and thoroughly mix. Failure to thoroughly mix the Part A and Part B components prior to thinning can affect product's gloss and performance. Do not use mixed material beyond pot life limits. **Note:** For application to surfaces between 35°F to 50°F (2°C to 10°C), allow mixed material to stand 30 minutes and restir before using.

THINNING

Use No. 4 or No. 60 Thinner. For air spray, thin up to 10% or 3/4 pint (380 mL) per gallon. For airless spray, roller or brush, thin up to 5% or 1/4 pint (190 mL) per gallon.

POT LIFE

2 hours at 50°F (10°C) 1 hour at 75°F (24°C) 30 minutes at 100°F (38°C)

SPRAY LIFE

30 minutes at 75°F (24°C)

Note: Spray application after listed times will adversely affect ability to achieve recommended dry film thickness.

HI-BUILD EPOXOLINE® II | SERIES N69F

APPLICATION EQUIPMENT

Air Spray •

Gun	Fluid Tip	Air Cap	Air Hose ID	Mat'l Hose ID	Atomizing Pressure	Pot Pressure
DeVilbiss JGA	E	765 or 704	5/16" or 3/8" (7.9 or 9.5 mm)	3/8" or 1/2" (9.5 or 12.7 mm)	50-80 psi (3.4-5.5 bar)	10-20 psi (0.7-1.4 bar)

Low temperatures or longer hoses require higher pot pressure.

Airless Spray •

Tip Orifice	Atomizing Pressure	Mat'l Hose ID	Manifold Filter
0.015"-0.019" (380-485 microns)	3000-4800 psi (207-330 bar)	1/4" or 3/8" (6.4 or 9.5 mm)	60 mesh (250 microns)

Use appropriate tip/atomizing pressure for equipment, applicator technique and weather conditions.

• Spray application of first coat on CMU should be followed by backrolling.

Note: Application over inorganic zinc-rich primers: Apply a wet mist coat and allow tiny bubbles to form. When bubbles disappear in 1 to 2 minutes, apply a full wet coat at specified mil thickness.

Roller: Use 3/8" or 1/2" (9.5 mm or 12.7 mm) synthetic woven nap roller cover. Use longer nap to obtain penetration on rough or porous surfaces.

Brush: Recommended for small areas only. Use high quality natural or synthetic bristle brushes.

SURFACE TEMPERATURE

Minimum 35°F (2°C) Maximum 135°F (57°C)

The surface should be dry and at least 5°F (3°C) above the dew point. Coating will not cure below minimum surface temperature.

CLEANUP

Flush and clean all equipment immediately after use with the recommended thinner or MEK.

† Values may vary with color.

WARRANTY & LIMITATION OF SELLER'S LIABILITY: Tnemec Company, Inc. warrants only that its coatings represented herein meet the formulation standards of Tnemec Company, Inc. THE WARRANTY DESCRIBED IN THE ABOVE PARAGRAPH SHALL BE IN LIEU OF ANY OTHER WARRANTY, EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. THERE ARE NO WARRANTIES THAT EXTEND BEYOND THE DESCRIPTION ON THE FACE HEREOF. The buyer's sole and exclusive remedy against Tnemec Company, Inc. shall be for replacement of the product in the event a defective condition of the product should be found to exist and the exclusive remedy shall not have failed its essential purpose as long as Tnemec is willing to provide comparable replacement product to the buyer. NO OTHER REMEDY (INCLUDING, BUT NOT LIMITED TO, INCIDENTAL OR CONSEQUENTIAL DAMAGES FOR LOST PROFITS, LOST SALES, INJURY TO PERSON OR PROPERTY, ENVIRONMENTAL INJURIES OR ANY OTHER INCIDENTAL OR CONSEQUENTIAL LOSS) SHALL BE AVAILABLE TO THE BUYER. Technical and application information herein is provided for the purpose of establishing a general profile of the coating and proper coating application procedures. Test performance results were obtained in a controlled environment and Tnemec Company makes no claim that these tests or any other tests, accurately represent all environments. As application, environmental and design factors can vary significantly, due care should be exercised in the selection and use of the coating.



SURFACING EPOXY SERIES 215

PRODUCT PROFILE

GENERIC DESCRIPTION

Modified Polyamine Epoxy

COMMON USAGE

An advanced generation, 100% solids epoxy filler and surfacer for concrete or steel. Excellent material for surfacing, patching, and filling voids in pitted steel and bug holes and pits in concrete substrates. Generally topcoated with a variety of high-performance epoxies and polyurethanes for use in mild to aggressive exposures.

COLORS

1200 White, 1212 Gray

FINISH

Semi-Gloss

SPECIAL QUALIFICATIONS

Certified by **NSF International** in accordance with **NSF/ANSI/CAN Std. 61** and the extraction requirements of **NSF/ANSI/CAN 600**. Series 215 is qualified for interior use on tanks and reservoirs. Reference Tnemec's certified product listing at www.nsf.org for additional details.

Series 215 meets the requirements of LEED-Low-Emitting Materials, Collaborative for High-Performance Schools-Paints & Coatings, WELL Building Standard-VOC Restrictions, and Living Building Challenge-Healthy Interior Performance. Contact your Tnemec representative for more information.

COATING SYSTEM

SURFACER/FILLER/PATCHER

Self-patching or Series 217, 218

PRIMERS

Steel: Self-priming, Series 1, 22, 66, L69, L69F, N69, N69F, V69, V69F, 90-97, H90-97, 90G-1K97, 91-H₂O, H91-H₂O, 94-H₂O, L140, L140F, N140, N140F, 161, 201, 394

Concrete: Self-priming, Series 22, 66, L69, L69F, N69, N69F, V69, V69F, L140, L140F, N140, N140F, 161, 201. **Note:** Primers may be necessary on some applications to minimize or eliminate the potential for outgassing. **Note:** For potable water mat lay-up system, use fiberglass mat product number S211-0215. For filtration membrane mat lay-up system, please reference the Series 215ML product data sheet.

CMU & Cement Board: Self-priming. Can also be used as a bedding coat for Series 273 Stranlok ML system, use fiberglass mat product number S273-0273C.

TOPCOATS

Series 22, FC22, 61, 66, L69, L69F, N69, N69F, V69, V69F, 104, 113, 114, 120-5002, L140, L140F, N140, N140F, 141, 161, 201, 210, 237SC, 239SC, 251SC, 262, 264, 270, 273, 280, 281, 282, 287, 406, 431, 434, 435, 436.

Note: Maximum recoat time for Series 406 is 72 hours.

SURFACE PREPARATION

STEEL

Non-Immersion Service: SSPC-SP6/NACE 3 Commercial Blast Cleaning with a minimum 3.0 mil angular anchor profile. **Immersion Service:** SSPC-SP10/NACE 2 Near-White Blast Cleaning with a minimum 3.0 mil angular anchor profile.

CONCRETE

Allow new cast-in-place concrete to cure a minimum of 28 days at 75°F (24°C). Verify concrete dryness in accordance with ASTM F 1869 "Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride" (moisture vapor transmission should not exceed three pounds per 1,000 square feet in a 24 hour period), F 2170 "Standard Test Method for Determining Relative Humidity in Concrete using in situ Probes" (relative humidity should not exceed 80%), or D 4263 "Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method" (no moisture present). Prepare concrete surfaces in accordance with NACE No. 6/SSPC-SP13 Joint Surface Preparation Standards and ICRI Technical Guidelines. Abrasive blast, shot-blast, water jet or mechanically abrade concrete surfaces to remove laitance, curing compounds, hardeners, sealers and other contaminants and to provide a minimum ICRI-CSP 5 surface profile. Large cracks, voids and other surface imperfections should be filled with a recommended filler or surfacer.

CMU

Allow mortar to cure for 14 days. Level protrusions and mortar spatter.

ALL SURFACES

Must be clean, dry and free of oil, grease, chalk and other contaminants.

TECHNICAL DATA

VOLUME SOLIDS

100% (mixed) †

RECOMMENDED DFT

Resurfacer: 1/32" to 1/8" (0.8 mm to 3.2 mm)

Up to 2" with the addition of Series 211 (see Mixing instructions) for filling honeycombs, blow holes, and surface imperfections found in formed concrete surfaces. Larger imperfections may require multiple applications. Bedding coat for mat lay up is typically in the 1/16" range.

CURING TIME

Temperature	To Touch	Dry Through	Maximum to Recoat ‡
95°F (35°C)	4 hours	12 hours	14 days
75°F (24°C)	10 hours	24 hours	21 days
55°F (13°C)	18 hours	48 hours	21 days
45°F (7°C)	24 hours	72 hours	21 days
35°F (2°C)	32 hours	96 hours	21 days

‡ **Note:** If the Series 215 surface is exterior exposed for more than seven days, scarification is required before topcoating. **Note:** Use "To Touch" cure information for minimum recoat times if succeeding topcoats are spray-applied and "Dry Through" if succeeding topcoats are applied by roller, brush, or trowel.

VOLATILE ORGANIC COMPOUNDS

Unthinned: 0.08 lbs/gal solids (10 grams/litre) †

HAPS

Unthinned: 0.0 lbs/gal solids

THEORETICAL COVERAGE

1,604 mil sq ft/gal (39.4 m²/L at 25 microns). See APPLICATION for coverage rates. †

NUMBER OF COMPONENTS

Two: Part A and Part B (1 Part A to 1 Part B by volume)

SURFACING EPOXY | SERIES 215

PACKAGING

	Part A	Part B	When Mixed
Large Kit	3 gallon pail (partial fill)	5 gallon pail (partial fill)	4 gallons (15 L)
Small Kit	1 gallon can	3 gallon pail (partial fill)	2 gallons (7.5 L)
Touch-Up Kit	1 quart can	1 quart can	1/2 gallon (1.89 L)

NET WEIGHT PER GALLON

13.28 ± 0.25 lbs (6.02 ± 0.11 kg) (mixed) †

STORAGE TEMPERATURE

Minimum 20°F (-6°C) Maximum 110°F (43°C)

Prior to application, the material temperature should be between 70°F and 80°F (21°C and 27°C). It is suggested the material be stored at these temperatures at least 48 hours prior to use.

TEMPERATURE RESISTANCE

(Dry) Continuous 250°F (121°C) Intermittent 275°F (135°C)

SHELF LIFE

12 months at recommended storage temperature.

FLASH POINT - SETA

Part A: >230°F (100°C) Part B: N/A

HEALTH & SAFETY

This product contains chemical ingredients which are considered hazardous. Read container label warning and Safety Data Sheet for important health and safety information prior to the use of this product.

Keep out of the reach of children.

APPLICATION

COVERAGE RATES

Thickness	Large Kit	Small Kit
1/32" (31 mils)	207 sq ft (19.2 m²)	103 sq ft (9.6 m²)
1/16" (62 mils)	103 sq ft (9.6 m²)	52 sq ft (4.8 m²)
1/8" (125 mils)	51 sq ft (4.8 m²)	26 sq ft (2.4 m²)
1/2" (500 mils)	13 sq ft (1.2 m²)	6 sq ft (0.6 m²)

MIXING

Mix the entire contents of Part A and Part B separately. Scrape all of the Part A material from the pail and into the Part B container by using a flexible spatula. Use a variable speed drill with a PS Jiffy blade and mix the blended components for a minimum of two minutes. Apply the mixed material within the pot life limits after agitation. **Note:** Tnemec Series 211-0211 fumed silica may be added at 0.75:1 by volume per mixed gallon where a thicker consistency is required to achieve the desired application and film build properties. Mix with Part A as directed in Mixing Instructions. Multiple lifts may be required. A large volume of material will gel quickly if not applied or reduced in volume.

Caution: Do not reseat mixed material. An explosion hazard may be created.

THINNING

Normally not required.

POT LIFE

45 minutes at 70°F (21°C) 25 minutes at 90°F (32°C)

Material temperatures above 90°F (32°C) will significantly reduce the pot life.

APPLICATION EQUIPMENT

Mortar hawk, trowels, broad knives and rubber floats are recommended. Series 215 can also be spray transferred using spray texture gun equipment.

Spray Application Equipment

Pump	Fluid Line	Spray Gun	Fluid Tips	Fluid Pressure	Atomizing Pressure	Hopper
WTWA 410 9:1 Ratio	25' 1" Diameter 10' 3/4" Diameter	WTWA Pole Gun	1/4" to 3/8"	180 to 360 psi (Adjust as necessary)	Adjust at gun for proper atomization	6.5 Gallons Stainless Steel
Graco 45:1, 56:1, X50, X60	3/8" to 1/2" I.D.	XTR-7	0.031"-0.041"	3500-4500 psi	N/A	6.5 Gallons Stainless Steel
Graco M680 10:1 Ratio	25' 1" Diameter 10' 3/4" Diameter	Flex Hose	No. 5 Nozzle	200 psi (Adjust as necessary)	Adjust at gun for proper atomization	10 Gallons Stainless Steel
Graco M680 10:1 Ratio	25' 1" Diameter 10' 3/4" Diameter	HTX	4C Fine Finish	250 psi (Adjust as necessary)	Adjust at gun for proper atomization	10 Gallons Stainless Steel

Cart mounted 9:1 ratio, air operated pump with air filter, regulator and lubricator, air control manifold, fluid outlet drain with drain valve and control air hose assembly. Refer to the operation manual for application instructions. Air requirements 80 CFM at 100 psi. **Atomization air must be dry, the use of an after cooler is recommended.**

SURFACE TEMPERATURE

Minimum 35°F (2°C), maximum 130°F (54°C). The surface temperature should be at least 5°F (3°C) above the dew point. Coating will not cure below minimum surface temperature. To minimize outgassing, concrete temperature should be stabilized or in a descending temperature mode and the concrete primed with a suitable epoxy primer.

MATERIAL TEMPERATURE

Prior to application, the material temperature should be between 70°F and 80°F (21°C and 27°C). It is suggested the material be stored at these temperatures at least 48 hours prior to use. Temperature will affect the workability. Cool temperatures increase viscosity and decrease workability. Warm temperatures will decrease viscosity and shorten pot life.

CLEANUP

Flush and clean all equipment immediately after use with xylene, MEK, or when required by SCAQMD regulations, No. 74 Thinner.


† Values may vary with color.

WARRANTY & LIMITATION OF SELLER'S LIABILITY: Tnemec Company, Inc. warrants only that its coatings represented herein meet the formulation standards of Tnemec Company, Inc. THE WARRANTY DESCRIBED IN THE ABOVE PARAGRAPH SHALL BE IN LIEU OF ANY OTHER WARRANTY, EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. THERE ARE NO WARRANTIES THAT EXTEND BEYOND THE DESCRIPTION ON THE FACE HEREOF. The buyer's sole and exclusive remedy against Tnemec Company, Inc. shall be for replacement of the product in the event a defective condition of the product should be found to exist and the exclusive remedy shall not have failed its essential purpose as long as Tnemec is willing to provide comparable replacement product to the buyer. NO OTHER REMEDY (INCLUDING, BUT NOT LIMITED TO, INCIDENTAL OR CONSEQUENTIAL DAMAGES FOR LOST PROFITS, LOST SALES, INJURY TO PERSON OR PROPERTY, ENVIRONMENTAL INJURIES OR ANY OTHER INCIDENTAL OR CONSEQUENTIAL LOSS) SHALL BE AVAILABLE TO THE BUYER. Technical and application information herein is provided for the purpose of establishing a general profile of the coating and proper coating application procedures. Test performance results were obtained in a controlled environment and Tnemec Company makes no claim that these tests or any other tests, accurately represent all environments. As application, environmental and design factors can vary significantly, due care should be exercised in the selection and use of the coating.


Site Overview



Lap Pool





Activity Pool



Lazy River






Plunge Pool



3' depth x 3' x 1' corner patch

Kiddie Pool





APPROVED

PERMIT # 61-2005
 DATE ISSUED 10/4/05
 REVIEWED BY CUS
 POOL NO. _____
 STATE OF ILLINOIS
 DEPARTMENT OF PUBLIC HEALTH
 BUREAU OF ENVIRONMENTAL HEALTH

VALVE VAULT
 SEE T OF SP-20

FILTER EQUIPMENT LAYOUT
 SEE T OF SP-11

DIVING POOL LAYOUT
 SEE T OF SP-4

ACTIVITY / LAP POOL LAYOUT
 SEE T OF SP-2

KIDDIE POOL LAYOUT
 SEE T OF SP-5

PLUNGE POOL LAYOUT
 SEE T OF SP-7

LAZY RIVER LAYOUT
 SEE T OF SP-6

1 AQUATIC FACILITY LAYOUT
 SCALE: 1/16" = 1'-0"


NOTE:
 I HEREBY CERTIFY THAT THE SWIMMING POOL IS DESIGNED AND IS
 TO BE CONSTRUCTED TO WITHSTAND ALL ANTICIPATED STRUCTURAL
 LOADING FOR BOTH FULL AND EMPTY CONDITIONS. MY SEAL AND
 SIGNATURE SHALL ENCOMPASS DRAWINGS SP-1 THROUGH SP-22.
 COPYRIGHT © 2004 INNOVATIVE AQUATIC DESIGN, LLC

COPYRIGHT © 2004
 Williams/Associates Architects, Ltd.

RECEIVED
 DIVISION OF
 ENVIRONMENTAL HEALTH
 SEP 17 2005

**CHAMPAIGN PARK DISTRICT
 SHOLEM POOL
 OUTDOOR AQUATIC FACILITY
 CHAMPAIGN, ILLINOIS 61821**

WEB NO. 2005-032
 DATE 21 MAR 2005
 CHECKED JML
 REVISION 12 APR 2005
 ADDENDUM NO. 1
 A T SEPT 2005-RF LHS
 A-2 SEPT 2005-ID P.H.




**INNOVATIVE
 AQUATIC DESIGN, LLC**
 38 SCULLY DRIVE, CHAMPAIGN, ILLINOIS 61821
 (847) 952-2858 FAX: (847) 952-3956

**WILLIAMS
 ARCHITECTS**
 ARCHITECTS PLANNERS
 210 North Hale, Wheaton, Illinois 60187
 Phone 630-221-1212 / Fax 630-221-1220



AQUATIC FACILITY
 LAYOUT

SP-1



ACTIVITY / LAP POOL EQUIPMENT LIST

THE EQUIPMENT MANUFACTURERS AND CATALOG NUMBERS LISTED BELOW, AND NOT SPECIFICALLY MENTIONED IN THE SPECIFICATIONS, ARE SHOWN TO PROVIDE A STANDARD. EQUIPMENT BY OTHER MANUFACTURERS WILL BE APPROVED IF SAID EQUIPMENT IS SHOWN TO BE EQUAL TO THAT SPECIFIED.

ITEM	DESCRIPTION	MANUFACTURER	CATALOG NO.	QTY.
1	FILTRATION PUMP AND MOTOR, FLOODED SUCTION, 1517 GPM @ 80 FT. TDH, 40 H.P., 480 VOLT, 3-PHASE, 1750 RPM, WITH NICKEL COATING ON ALL CAST IRON PARTS INSIDE AND OUT.	PACO	60123LC	1
2	PLAY FEATURE PUMP AND MOTOR, FLOODED SUCTION, 390 GPM @ 40 FT. TDH, 5 H.P., 480 VOLT, 3-PHASE, 1750 RPM, WITH NICKEL COATING ON ALL CAST IRON PARTS INSIDE AND OUT.	PACO	40707LC	1
3	VARIABLE FREQUENCY DRIVE, 480 VOLT, 3-PHASE, 60 Hz, WITH NEMA 1 ENCLOSURE, INTEGRAL DISCONNECT AND LINE REACTOR, HORSE POWER AS REQUIRED FOR EACH PUMP MOTOR.	ROBICON	454GT	2
4	STRAINER, PVC, 12", STRAIGHT, WITH TWO STAINLESS STEEL BASKETS.	NEPTUNE BENSON	NBPVCSTR12	1
5	STRAINER, PVC, 8" x 5" REDUCING STYLE, WITH TWO STAINLESS STEEL BASKETS.	NEPTUNE BENSON	NBPVCSTE85	1
6	VACUUM / PRESSURE GAUGE, 0" - 30" AND 0 - 60 PSI, 2 1/2" DIAL, LIQUID FILLED, WITH STAINLESS STEEL TUBE AND SOCKET, SNUBBER NO. 872-2 AND GAUGE COCK NO. 865MFG.	TRERICE	700	2
7	PRESSURE GAUGE, 0 - 60 PSI, 2 1/2" DIAL, LIQUID FILLED, WITH STAINLESS STEEL TUBE AND SOCKET, SNUBBER NO. 872-2 AND GAUGE COCK NO. 865MFG.	TRERICE	700	2
8	POOL WATER HEATER, NATURAL GAS, 1,260,000 BTU INPUT, WITH AUTOMATIC HIGH LIMIT SHUT-OFF, ASME PRESSURE RELIEF VALVE AND ASME CODE AND LABEL.	LOCHINVAR	CPN-1261	2
9	THERMOMETER, 30° TO 130° FAHRENHEIT RANGE WITH SEPARABLE WELL NO. 138-0015.2.	TRERICE	A40543	4
10	ELECTROMAGNETIC FLOW SENSOR FOR FILTRATION PUMP AND MOTOR VARIABLE FREQUENCY DRIVE CONTROL.	SIGNET	2550	1
11	FLOOR INLET FLOW METER, 6", WITH 0 - 800 GPM SCALE RANGE AND FLOW SENSOR NO. P51530-P1.	SIGNET	5090	1
12	GUTTER INLET FLOW METER, 8", WITH 0 - 1500 GPM SCALE RANGE AND FLOW SENSOR NO. P51530-P1.	SIGNET	5090	1
13	LAP AREA CHLORINE METERING PUMP, 185 GPD CAPACITY, 110 VOLT, 1-PHASE.	STENNER	85M5	1
14	LAP AREA ACID METERING PUMP, 50 G.P.D. CAPACITY, 110 VOLT, 1-PHASE.	STENNER	45M5	1
15	ACTIVITY AREA CHLORINE METERING PUMP, 85 GPD CAPACITY, 110 VOLT, 1-PHASE.	STENNER	85M5	1
16	ACTIVITY AREA ACID METERING PUMP, 22 GPD CAPACITY, 110 VOLT, 1-PHASE.	STENNER	45M3	1
17	AUTOMATIC CHEMICAL CONTROLLER, 110 VOLT, 1-PHASE, WITH WS/RAK SAMPLE STREAM ASSEMBLY AND INTEGRAL MODEM.	STRANTRON	SYSTEM 5	2
18	CHEMICAL CONTROLLER SAMPLE STREAM PUMP AND MOTOR, SELF-PRIMING, 15 GPM @ 25 FT. TDH, 110 VOLT, 1-PHASE, WITH INTEGRAL STRAINER.	PENTAIR	AFP-75	2
19	ENZYME CLEANING SYSTEM WITH AUTOMATIC DOSAGE DISPENSER.	NATURAL CHEM.	-----	1
20	AUTOMATIC WATER LEVEL CONTROLLER WITH PROBE NO. A94-10 AND ELEVEN POLE BASE NO. 5411.	ELECTROMATIC	5194	1
21	FIBERGLASS SUMP FOR SURGE TANK DRAIN W/ 9" x 9" FRAME AND GRATE.	PENTAIR	543099	1
22	TEST KIT.	TAYLOR	K-1741C	1
23	STAINLESS STEEL PERIMETER OVERFLOW AND RECIRCULATION SYSTEM W/ 107 - 716" DIA. INLETS.	SEE SPECIFICATION	SEE SPECIFICATION	PER PLAN
24	FIBERGLASS SAMPLE STREAM DRAIN SUMP WITH 12" x 12" FRAME AND GRATE, O.A. = 86 SQ. IN.	PENTAIR	543035	2
25	FIBERGLASS MAIN DRAIN SUMP WITH 18" x 18" FRAME AND GRATE, O.A. = 136 SQ. IN.	PENTAIR	543088	4
26	HYDROSTATIC RELIEF VALVE.	HAYWARD	SP-1056	4
27	COLLECTION TUBE FOR HYDROSTATIC RELIEF VALVE.	HAYWARD	SP-1055	4
28	FLOOR INLET, 1 1/2".	STA-RITE	8417-0000	19
29	ZERO DEPTH GUTTER GRATING, 12" WIDTH, COLOR: WHITE.	GRATE TECHNOLOGY	-----	PER PLAN
30	WEDGE ANCHOR, BRONZE.	PARAGON AQUA.	28102	2G
31	ESCUTCHEON PLATE, STAINLESS STEEL.	PARAGON AQUA.	28302	2G
32	GRAB RAILS, STAINLESS STEEL, WITH .109" TUBING WALL THICKNESS.	PARAGON AQUA.	30102	5PR.
33	RECESSED STEP, STAINLESS STEEL.	PARAGON AQUA.	32104	11
34	HAND RAIL, STAINLESS STEEL, WITH .109" TUBING WALL THICKNESS.	PARAGON AQUA.	CUSTOM	3
35	ANCHORS FOR STARTING PLATFORMS.	PARAGON AQUA.	23103	6
36	ANCHORS FOR BACKSTROKE AND RECALL STANCHIONS.	PARAGON AQUA.	38210	6
37	HYDRAULIC HANDICAP LIFT.	SPECTRUM	27336	1
38	PORTABLE LIFE GUARD CHAIR.	PARAGON AQUA.	20370	6
39	TUMBLE BUCKETS.	RAIN DROP	TBKT-001	1
40	TOT SLIDE.	F.A.S.T.	9064	1
41	SLIDE PAD, 3'-0" x 4'-0".	NBGS INTL.	-----	1
42	PORTABLE GAS POWERED VACUUM PUMP, 3 H.P. WITH INTEGRAL STRAINER AND 2 WHEEL CHASSIS.	MARLOW	2AF1-B	1
43	VACUUM HEAD, 24", WITH SWIVEL WHEELS.	QUALITY	215	1
44	VACUUM HOSE, 2" x 50'-0".	AQUALITY	PROFLO	1
45	TELESCOPIC POLE FOR VACUUM SET, 12 FT. TO 22 FT., ALUMINUM.	AQUALITY	4003	3
46	LEAF RAKE.	AQUALITY	6003	1
47	WALL BRUSH.	AQUALITY	7003	1
48	FIRST AID KIT, W/MOUNTING CASE, PER ILLINOIS DEPT. OF PUBLIC HEALTH.	LINCOLN EQUIP.	47-095	1
49	AQUASTAT, SET TO 115° FAHRENHEIT.	HONEYWELL	L400GA1959	1
50	BERNOULLI PLAY CENTER.	VORTEX	VOR-1201	1


DATA	ACTIVITY POOL	LAP POOL	TOTAL
SURFACE AREA:	7,432 SQ. FT.	4,350 SQ. FT.	11,782 SQ. FT.
PERIMETER:	-	-	-
WATER DEPTHS:	0' to 4'-4"	3'-6" to 5'-0"	0' to 5'-0"
CAPACITY:	86,397 GALLONS	133,545 GALLONS	219,942 GALLONS
FILTER FLOWRATE:	960 G.P.M.	557 G.P.M.	1,517 G.P.M.
TURNOVER RATE:	90 MINUTES	4 HOURS	-

DEPTH MARKER LEGEND

KEY	DEPTH	QUANTITY
1	1 FT. 0 IN.	2
2	2 FT. 0 IN.	2
3	3 FT. 0 IN.	2
4	3 FT. 6 IN.	5
5	4 FT. 0 IN.	1
6	4 FT. 6 IN.	2
7	5 FT. 0 IN.	5


NOTE:

DEPTH MARKERS ON POOL DECK EDGE AND CONCRETE POOL WALL TO BE 4" HIGH ON 6" X 6" CERAMIC TILE WITH A NO - DIVING SYMBOL CERAMIC TILE AT EACH LOCATION OF 5'-0" WATER DEPTH OR LESS. PROVIDE 4" HIGH VINYL DEPTH MARKERS ON FACE OF STAINLESS STEEL GUTTER BACK. ALL NUMERALS AND LETTERS TO BE A COLOR WHICH IS CONTRASTING TO THEIR BACKGROUND. TILE TO BE INLAID FLUSH WITH CONCRETE SURFACE.



1 ACTIVITY POOL LAYOUT
SCALE: 1/8" = 1'-0"

waa no	2003-032
date	21 MAR. 2005
drawn	RRD
checked	JML
revised	12 APR. 2005
	APPENDUM NO.1
	1 SEPT. 2005
	I.D.P.H. PERMIT




INNOVATIVE



AQUATIC DESIGN, LLC
39 SCULLY DRIVE, SCHAMBURG, ILLINOIS 60183
(847) 352-2958 FAX: (847) 352-3596


**WILLIAMS
ARCHITECTS
ARCHITECTS PLANNERS**
10 North Hale, Wheaton, Illinois 60187
phone 630-221-1212 / Fax 630-221-1220




ACTIVITY / LAP
POOL SECTIONS

SP-3





1 KID'S POOL LAYOUT
SCALE: 1/4" = 1'-0"




2 KID'S POOL CROSS SECTION
SCALE: 1/4" = 1'-0"

DEPTH MARKER LEGEND

KEY	DEPTH	QUANTITY
1	0 FT. 6 IN.	2
2	1 FT. 0 IN.	2
3	1 FT. 4 IN.	2
4	1 FT. 6 IN.	1

NOTE:
DEPTH MARKERS ON POOL DECK EDGE AND CONCRETE POOL WALL TO BE 4" HIGH ON 6" X 6" CERAMIC TILE WITH A NO - DIVING SYMBOL CERAMIC TILE AT EACH LOCATION OF 5'-0" WATER DEPTH OR LESS. PROVIDE 4" HIGH VINYL DEPTH MARKERS ON FACE OF STAINLESS STEEL GUTTER BACK. ALL NUMERALS AND LETTERS TO BE A COLOR WHICH IS CONTRASTING TO THEIR BACKGROUND. TILE TO BE INLaid FLUSH WITH CONCRETE SURFACE.

DATA	KID'S POOL
SURFACE AREA:	1,041 SQ. FT.
PERIMETER:	-
WATER DEPTHS:	0' to 1'-6"
CAPACITY:	5,409 GALLONS
FILTER FLOWRATE:	91 G.P.M.
TURNOVER RATE:	60 MINUTES



3 KID'S POOL LONGITUDINAL SECTION
SCALE: 1/4" = 1'-0"


KID'S POOL EQUIPMENT LIST

THE EQUIPMENT MANUFACTURERS AND CATALOG NUMBERS LISTED BELOW, AND NOT SPECIFICALLY MENTIONED IN THE SPECIFICATIONS, ARE SHOWN TO PROVIDE A STANDARD EQUIPMENT BY OTHER MANUFACTURERS WILL BE APPROVED IF SAID EQUIPMENT IS SHOWN TO BE EQUAL TO THAT SPECIFIED.


ITEM	DESCRIPTION	MANUFACTURER	CATALOG NO.	QTY.
A	FILTER, HI-RATE SAND, 36" DIA, W/ 7.06 SQ. FT. OF FILTER AREA, 12.9 GPM/SQ. FT. FILTRATION RATE, COMPLETE WITH PRESSURE GAUGE AND MANUAL AIR RELEASE VALVE.	PENTAIR	TR-140C	1
B	FILTRATION PUMP AND MOTOR, FLOODED SUCTION, 91 GPM @ 70 FT. HEAD, 3 H.P., 480 VOLT, 3-PHASE, 1750 RPM, WITH NICKEL COATING ON ALL CAST IRON PARTS INSIDE AND OUT.	PACO	15959LC	1
C	PLAY FEATURE PUMP AND MOTOR, FLOODED SUCTION, 150 GPM @ 40 FT. HEAD, 2 H.P., 480 VOLT, 3-PHASE, 1750 RPM, W/ NICKEL COATING ON ALL CAST IRON PARTS INSIDE AND OUT.	PACO	20709LC	1
D	VARIABLE FREQUENCY DRIVE, 480 VOLT, 3-PHASE, 60 Hz, WITH NEMA 1 ENCLOSURE, INTEGRAL DISCONNECT AND LINE REACTOR, HORSE POWER AS REQUIRED FOR EACH MOTOR.	ROBICON	454GT	2
E	STRAINER, PVC, 4" X 2" REDUCING STYLE, WITH TWO STAINLESS STEEL BASKETS	NEPTUNE BENSON	NBPVCSTE42	1
F	STRAINER, PVC, 4" X 2 1/2" REDUCING STYLE, WITH TWO STAINLESS STEEL BASKETS	NEPTUNE BENSON	NBPVCSTE45	1
G	HEATER, NATURAL GAS, 300,000 BTU INPUT, WITH 5" AIR INTAKE VENT AND 5" EXHAUST VENT, AUTOMATIC HIGH LIMIT SHUTOFF, ASME PRESSURE RELIEF VALVE AND ASME CODE AND LABEL.	LOCHINVAR	ERN-301	1
H	THERMOMETER, 30° TO 130° FAHRENHEIT RANGE WITH SEPARABLE WELL NO. 138-0015.2.	TRERICE	A40543	3
J	VACUUM / PRESSURE GAUGE, 0° TO 30° AND 0 TO 60 PSI, 2 1/2" DIAL, LIQUID FILLED, WITH STAINLESS STEEL TUBE AND SOCKET, SNUBBER NO. 872-2 AND GAUGE COCK NO. 865MFG.	TRERICE	700	2
K	PRESSURE GAUGE, 0 TO 60 PSI, 2 1/2" DIAL, LIQUID FILLED, WITH STAINLESS STEEL TUBE AND SOCKET, SNUBBER NO. 872-2 AND GAUGE COCK NO. 865MFG.	TRERICE	700	3
L	ELECTROMAGNETIC FLOW SENSOR FOR FILTRATION PUMP AND MOTOR VARIABLE FREQUENCY DRIVE CONTROL.	SIGNET	2550	1
M	CHLORINE METERING PUMP, 22 GPD CAPACITY, 110 VOLT, 1-PHASE.	STENNER	45M3	1
N	ACID METERING PUMP, 10 GPD CAPACITY, 110 VOLT, 1-PHASE.	STENNER	45M2	1
O	AUTOMATIC CHEMICAL CONTROLLER, 110 VOLT, 1-PHASE, WITH WS/RAC SAMPLE STREAM ASSEMBLY AND INTEGRAL MODEM.	STRANTROL	SYSTEM 5	1
P	AUTOMATIC WATER LEVEL CONTROLLER W/ PROBE NO. A94-10 AND ELEVEN POLE BASE NO. S411.	ELECTROMATIC	5194	1
Q	STAINLESS STEEL GUTTER SYSTEM WITH PVC OR FIBERGLASS GRATING	SEE SPECIFICATION	CUSTOM	SEE PLAN
R	INLET FITTINGS, FLOOR TYPE, 1 1/2".	STA-RITE	8417-0000	5
S	FIBERGLASS MAIN DRAIN SUMP WITH 18" x 18" FRAME AND GRATE, OPEN AREA = 196 SQ. IN.	PENTAIR	543088	2
T	HYDROSTATIC RELIEF VALVE.	HAYWARD	SP-1056	2
U	HYDROSTATIC COLLECTION TUBE.	HAYWARD	SP-1055	2
V	ZERO DEPTH GUTTER GRATING, 12" WIDTH, COLOR: WHITE	GRATE TECHNOLOGY	-----	SEE PLAN
W	FIBERGLASS SUMP FOR SURGE TANK DRAIN WITH 9" x 9" FRAME AND GRATE.	PENTAIR	543099	1
X	KID'S SLIDE.	FAST CORP.	9132	1
Y	SLIDE PAD, 3'-0" X 4'-0".	NBGS INTL.	-----	1
Z	AQUASTAT, SET TO 115° FAHRENHEIT.	HONEYWELL	L4006A1959	1

ALTERNATE #1

DATA	PLUNGE POOL	LAZY RIVER	TOTAL
SURFACE AREA:	1,474 SQ. FT.	11,094 SQ. FT.	12,568 SQ. FT.
PERIMETER:	172'-0"	-	-
WATER DEPTHS:	3'-0" to 3'-8"	0'-0" to 3'-0"	-
CAPACITY:	37,274 GALLONS	232,388 GALLONS	269,662 GALLONS
FILTER FLOWRATE:	311 G.P.M.	1,937 G.P.M.	2,248 G.P.M.
TURNOVER RATE:	2 HOURS	2 HOURS	2 HOURS



2 LAZY RIVER LONGITUDINAL SECTION
SCALE: 1/4" = 1'-0"



1 LAZY RIVER LAYOUT
SCALE: 3/32" = 1'-0"


DEPTH MARKER LEGEND

KEY	DEPTH	QUANTITY
1	1 FT. 0 IN.	2
2	2 FT. 0 IN.	2
3	2 FT. 8 IN.	1
4	3 FT. 0 IN.	24

NOTE:
DEPTH MARKERS ON POOL DECK EDGE AND CONCRETE POOL WALL TO BE 4" HIGH ON 6" X 6" CERAMIC TILE WITH A NO - DIVING SYMBOL CERAMIC TILE AT EACH DECK LOCATION. ALL NUMERALS AND LETTERS TO BE A COLOR WHICH IS CONTRASTING TO THEIR BACKGROUND. DEPTH MARKERS AND NO-DIVING SYMBOLS ARE REQUIRED ON THE POOL DECK ONLY WHERE THE DECK IS ADJACENT TO A POOL WALL.


CHAMPAIGN PARK DISTRICT
SHOLEM POOL
OUTDOOR AQUATIC FACILITY
CHAMPAIGN, ILLINOIS 61821

2003-03-25
21 MAR 2005
21 MAR 2005
12 APR 2005
11 SEPT 2005
11 SEPT 2005
11 SEPT 2005
11 SEPT 2005




INNOVATIVE
AQUATIC DESIGN, LLC
38 SCULLY DRIVE, CHAMPAIGN, ILLINOIS 61821
(847) 382-2988 FAX: (847) 382-2988

WILLIAMS
ARCHITECTS
ARCHITECTS PLANNERS
210 North Hale, Wheaton, Illinois 60187
Phone 630-221-1212 / Fax 630-221-1220








LAZY RIVER LAYOUT,
SECTION, DATA AND
DEPTH MARKER
LEGEND

SP-6


[illegible]

COPYRIGHT © 2004 INNOVATIVE AQUATIC DESIGN, LLC




CHAMPAIGN PARK DISTRICT
SHOLEM POOL
OUTDOOR AQUATIC FACILITY
CHAMPAIGN, ILLINOIS 61821

was no.	2005-032
date	21 MAR 2005
drawn	JUL
checked	12 APR 2005
revised	ADENDUM NO. 1
ADENDUM NO. 1	1 SEPT. 2005
I.D.P.H. PERMIT	









INNOVATIVE
AQUATIC DESIGN, LLC
39 SCULLY DRIVE, CHAMPAIGN, ILLINOIS 61821
(847) 352-2958 FAX: (847) 352-3595


WILLIAMS
ARCHITECTS
ARCHITECTS PLANNERS
210 North Hale, Wheaton, Illinois 60187
Phone 630-221-1212 / Fax 630-221-1220



PLUNGE POOL AND
DEEP POOL
STRUCTURAL LAYOUTS
AND STRUCTURAL
DETAILS

SP-9





STATIC WATER LEVEL - EL. 725.08'
TOP OF LAZY RIVER WALL - EL. 725.92'

LAZY RIVER STRUCTURAL LAYOUT